

Lytchett Matravers Recreation Ground

Proposed measures to help prevent unauthorised incursions



KEY

Small Earth Bund (0.5m high)
Total length approx = 75m
x approx 1 tonne per 2m metre length x £5/tonne = £400
+ Dumper hire for 1 week = £150
+ Digger hire for 1 week = £250
TOTAL = £800+VAT

3x Height restriction gates
(using existing pillars at High Street)

one at 4m, two at 5.6m.
Comprising 150 x 150mm box section hanging posts, 100 x 100mm slam posts, including 100 x 1000mm hold open posts, all galvanised and powder coated RAL6005 Green, with signs in red and white showing the height. Cost = £4250
+ 3x combination padlocks at approx £10 each



TOTAL = £4280+VAT

GRAND TOTAL = £5080+VAT